

Overview of NuScale Technology



D. T. Ingersoll

Director of Research Collaborations

June 12, 2012


33rd Annual CNS Conference



Deliberately Small for Safety and Affordability

KEY: Scalable plant design based on robust 45 MWe module

- Integral PWR design with natural circulation of primary coolant
- Steel containment vessel immersed in 4 million gallon pool
- Factory fabricated and truck transportable to site
- Staggered build-out to match demand growth and reduce cash outlay





540 MWe "12 Pack" Reference Plant




45 MWe Module

NuScale Module: NSSS and Containment



Passively Safe and Robust Modules

- **Natural Convection for Cooling**
 - Inherently safe natural circulation of water driven by gravity cools the nuclear fuel
 - No pumps required to continuously provide water for safety functions
- **Seismically Robust**
 - System is submerged in a pool of water below ground in an earthquake resistant building
 - Reactor pool attenuates ground motion and dissipates energy
- **Defense-in-Depth**
 - Multiple additional barriers to protect against the release of radiation to the environment




Modules in Robust Reactor Building and Pool

12-module, 540 MWe NuScale Plant

NuScale nuclear power reactors are housed inside high strength (10x) steel containment vessels and submerged in 4 million gallons of water below ground level inside the Reactor Building.

The Reactor Building is designed to withstand earthquakes, floods, tornados, hurricane force winds, and aircraft impacts.




Reactor pool sufficiently large to provide all modules with 30-day supply of cooling water.

Any hydrogen released is trapped in containment vessel with little or no oxygen available to create a combustible mixture.

Decay Heat Removal From Containment

- Provides a means of removing core decay heat and limits containment pressure by:
 - Steam Condensation
 - Convective Heat Transfer
 - Heat Conduction
 - Sump Recirculation
- Reactor Vessel steam is vented through the reactor vent valves (flow limited)
- Steam condenses on containment
- Condensate collects in lower containment region
- Reactor Recirculation Valves open to provide recirculation path through the core
- Provides 30+ day cooling followed by indefinite period of air cooling.




Stable Long Term Cooling


Reactor and nuclear fuel cooled indefinitely without pumps or power



No Pumps • No External Power • No External Water



Module Assembly Operations




Modularity Is Key to Scalability

Reference Plant: 12 modules @ 45 MWe each produces 540 MWe


Allows for staggered installation and refueling of modules



Cross-sectional View of Reactor Building



Incremental Build Out



NuScale Site layout



Innovation Requires Robust Testing Program



Full System Safety Tests



Fabricating and Testing Major Components

- Steam Generator
- Handling Equipment
- Control Rod Drive Mechanisms
- Passive Safety Systems
- Valves
- Inspection Equipment
- Fuel Bundles
- Main Control Room



Separate Effect Tests

- Fuel Assembly Flow Testing
- Fuel Grid Structural Crush Testing
- Fuel Rod Critical Heat Flux Testing
- Containment High Pressure Condensation
- Steam Generator Heat Transfer Evaluation



*1100 NE Circle Blvd, Suite 350
Corvallis, OR 97330
541-207-3931
<http://www.nuscalepower.com>*

dingersoll@nuscalepower.com

